

P. INT COOPERATION TREA

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

From the INTERNATIONAL BUREAU

To:

United States Patent and Trademark
Office
(Box PCT)
Crystal Plaza 2
Washington, DC 20231
ÉTATS-UNIS D'AMÉRIQUE

in its capacity as elected Office

Date of mailing (day/month/year) 05 July 1999 (05.07.99)	
International application No. PCT/IL98/00568	Applicant's or agent's file reference 114481.5 RS
International filing date (day/month/year) 20 November 1998 (20.11.98)	Priority date (day/month/year) 20 November 1997 (20.11.97)
Applicant KOLTUNOV, Yoseph et al	

1. The designated Office is hereby notified of its election made:

☒ in the demand filed with the International Preliminary Examining Authority on:
02 June 1999 (02.06.99)

☐ in a notice effecting later election filed with the International Bureau on:

2. The election ☒ was
☐ was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

<p>The International Bureau of WIPO 34, chemin des Colombettes 1211 Geneva 20, Switzerland</p> <p>Facsimile No.: (41-22) 740.14.35</p>	<p>Authorized officer S. Mafla</p> <p>Telephone No.: (41-22) 338.83.38</p>
--	--



REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

Receiving Office use only

International Application No.

International Filing Date

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(if desired) (12 characters maximum) 114481.5 RS

Box No. I TITLE OF INVENTION DETERMINATION OF TEMPERATURE AND/OR EMISSIVITY FUNCTION OF OBJECTS BY REMOTE SENSING	
Box No. II APPLICANT	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.) ISRAEL AIRCRAFT INDUSTRIES LTD., TAMAM DIVISION P.O.Box 75 Yahud 56100 Israel	
<input type="checkbox"/> This person is also inventor.	
Telephone No.	
Facsimile No.	
Teleprinter No.	
State (that is, country) of nationality: IL	State (that is, country) of residence: IL
This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input checked="" type="checkbox"/> all designated States except the United States of America <input type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box	
Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.) KOLTUNOV, Yoseph 10/20 Avivim Street Holon 58267 Israel	
This person is: <input type="checkbox"/> applicant only <input checked="" type="checkbox"/> applicant and inventor <input type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)	
State (that is, country) of nationality: IL	State (that is, country) of residence: IL
This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box	
<input checked="" type="checkbox"/> Further applicants and/or (further) inventors are indicated on a continuation sheet.	
Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE	
The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: <input checked="" type="checkbox"/> agent <input type="checkbox"/> common representative	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.) REINHOLD COHN AND PARTNERS P.O.Box 4060 Tel-Aviv 61040 Israel	
Telephone No. +972 3 7109312/3	
Facsimile No. +972 3 5606405	
Teleprinter No.	
<input type="checkbox"/> Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.	

Continuation of Box No. III FURTHER APPLICANTS AND/OR (FURTHER) INVENTOR(S)

If none of the following sub-boxes is used, this sheet is not to be included in the request.

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

MAXIMOV, Alexander
17/20 Haarazim Street
Jerusalem 96181
Israel

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:
IL

State (that is, country) of residence:
IL

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

MEITIN, Igor
7/30 Ben-Gurion Street
Giv'at Shmuel 54018
Israel

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:
IL

State (that is, country) of residence:
IL

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

ALLON, Motti
44 Rabinovitz Street
Holon 58672
Israel

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:
IL

State (that is, country) of residence:
IL

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

GUTTMAN, Glen D.
39 Sderot Chen
Tel-Aviv 64166
Israel

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:
IL

State (that is, country) of residence:
IL

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

☒ Further applicants and/or (further) inventors are indicated on another continuation sheet.

Continuation of Box No. III FURTHER APPLICANTS AND/OR (FURTHER) INVENTOR(S)

If none of the following sub-boxes is used, this sheet is not to be included in the request.

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

KERSHENBAUM, Arik
3/1 Moshe Dayan Street
Ra'anana 43580
Israel

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:
IL

State (that is, country) of residence:
IL

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

This person is:

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

This person is:

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

This person is:

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on another continuation sheet.

Box No.V DESIGNATION STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

Regional Patent

- ☒ **AP ARIPO Patent:** GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SZ Swaziland, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☒ **EA Eurasian Patent:** AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ **EP European Patent:** AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☒ **OA OAPI Patent:** BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | |
|--|--|
| <input checked="" type="checkbox"/> AL Albania | <input checked="" type="checkbox"/> LS Lesotho |
| <input checked="" type="checkbox"/> AM Armenia | <input checked="" type="checkbox"/> LT Lithuania |
| <input checked="" type="checkbox"/> AT Austria | <input checked="" type="checkbox"/> LU Luxembourg |
| <input checked="" type="checkbox"/> AU Australia | <input checked="" type="checkbox"/> LV Latvia |
| <input checked="" type="checkbox"/> AZ Azerbaijan | <input checked="" type="checkbox"/> MD Republic of Moldova |
| <input checked="" type="checkbox"/> BA Bosnia and Herzegovina | <input checked="" type="checkbox"/> MG Madagascar |
| <input checked="" type="checkbox"/> BB Barbados | <input checked="" type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input checked="" type="checkbox"/> BG Bulgaria | |
| <input checked="" type="checkbox"/> BR Brazil | <input checked="" type="checkbox"/> MN Mongolia |
| <input checked="" type="checkbox"/> BY Belarus | <input checked="" type="checkbox"/> MW Malawi |
| <input checked="" type="checkbox"/> CA Canada | <input checked="" type="checkbox"/> MX Mexico |
| <input checked="" type="checkbox"/> CH and LI Switzerland and Liechtenstein | <input checked="" type="checkbox"/> NO Norway |
| <input checked="" type="checkbox"/> CN China | <input checked="" type="checkbox"/> NZ New Zealand |
| <input checked="" type="checkbox"/> CU Cuba | <input checked="" type="checkbox"/> PL Poland |
| <input checked="" type="checkbox"/> CZ Czech Republic | <input checked="" type="checkbox"/> PT Portugal |
| <input checked="" type="checkbox"/> DE Germany | <input checked="" type="checkbox"/> RO Romania |
| <input checked="" type="checkbox"/> DK Denmark | <input checked="" type="checkbox"/> RU Russian Federation |
| <input checked="" type="checkbox"/> EE Estonia | <input checked="" type="checkbox"/> SD Sudan |
| <input checked="" type="checkbox"/> ES Spain | <input checked="" type="checkbox"/> SE Sweden |
| <input checked="" type="checkbox"/> FI Finland | <input checked="" type="checkbox"/> SG Singapore |
| <input checked="" type="checkbox"/> GB United Kingdom | <input checked="" type="checkbox"/> SI Slovenia |
| <input checked="" type="checkbox"/> GE Georgia | <input checked="" type="checkbox"/> SK Slovakia |
| <input checked="" type="checkbox"/> GH Ghana | <input checked="" type="checkbox"/> SL Sierra Leone |
| <input checked="" type="checkbox"/> GM Gambia | <input checked="" type="checkbox"/> TJ Tajikistan |
| <input type="checkbox"/> GW Guinea-Bissau | <input checked="" type="checkbox"/> TM Turkmenistan |
| <input checked="" type="checkbox"/> HR Croatia | <input checked="" type="checkbox"/> TR Turkey |
| <input checked="" type="checkbox"/> HU Hungary | <input checked="" type="checkbox"/> TT Trinidad and Tobago |
| <input checked="" type="checkbox"/> ID Indonesia | <input checked="" type="checkbox"/> UA Ukraine |
| <input checked="" type="checkbox"/> IL Israel | <input checked="" type="checkbox"/> UG Uganda |
| <input checked="" type="checkbox"/> IS Iceland | <input checked="" type="checkbox"/> US United States of America |
| <input checked="" type="checkbox"/> JP Japan | |
| <input checked="" type="checkbox"/> KE Kenya | <input checked="" type="checkbox"/> UZ Uzbekistan |
| <input checked="" type="checkbox"/> KG Kyrgyzstan | <input checked="" type="checkbox"/> VN Viet Nam |
| <input checked="" type="checkbox"/> KP Democratic People's Republic of Korea | <input checked="" type="checkbox"/> YU Yugoslavia |
| | <input checked="" type="checkbox"/> ZW Zimbabwe |
| <input checked="" type="checkbox"/> KR Republic of Korea | Check-boxes reserved for designating States (for the purposes of |
| <input checked="" type="checkbox"/> KZ Kazakhstan | a national patent) which have become party to the PCT after |
| <input checked="" type="checkbox"/> LC Saint Lucia | issuance of this sheet: |
| <input checked="" type="checkbox"/> LK Sri Lanka | <input checked="" type="checkbox"/> GD- Grenada |
| <input checked="" type="checkbox"/> LR Liberia | <input type="checkbox"/> |

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIM		<input type="checkbox"/> Further priority claims are indicated in the Supplemental Box.		
Filing date of earlier application (day/month/year)	Number of earlier application	With earlier application is:		
		national application: country	regional application:* regional Office	international application: receiving Office
item (1) 20 November 1997 (20.11.97)	122258	IL		
item (2)				
item (3)				

☒ The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s): (1)

* Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA)
(if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):

ISA/EP

Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):

Date (day/month/year) Number Country (or regional Office)

Box No. VIII CHECK LIST: LANGUAGE OF FILING

This international application contains the following number of sheets:

request : 5
description (excluding sequence listing part) : 36
claims : 11
abstract : 1
drawings : 8
sequence listing part of description :
Total number of sheets : 61

This international application is accompanied by the item(s) marked below:

1. ☒ fee calculation sheet
2. ☒ separate signed power of attorney
3. ☐ copy of general power of attorney; reference number, if any:
4. ☐ statement explaining lack of signature
5. ☐ priority document(s) identified in Box No. VI as item(s):
6. ☐ translation of international application into (language):
7. ☐ separate indications concerning deposited microorganism or other biological material
8. ☐ nucleotide and/or amino acid sequence listing in computer readable form
9. ☐ other (specify):

Figure of the drawings which should accompany the abstract:

7

Language of filing of the international application:

ENGLISH

Box No. IX SIGNATURE OF APPLICANT OR AGENT

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).



LEVIN Elena
Agent for REINHOLD COHN AND PARTNERS

For receiving Office use only		2. Drawings: <input type="checkbox"/> received: <input type="checkbox"/> not received:
1. Date of actual receipt of the purported international application:		
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:		
4. Date of timely receipt of the required corrections under PCT Article 11(2):		
5. International Searching Authority (if two or more are competent): ISA/	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid	

For International Bureau use only	
Date of receipt of the record copy by the International Bureau:	

PCT

INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference 114481.5 RS	FOR FURTHER ACTION see Notification of Transmittal of International Search Report (Form PCT/ISA/220) as well as, where applicable, item 5 below.	
International application No. PCT/IL 98/ 00568	International filing date (day/month/year) 20/11/1998	(Earliest) Priority Date (day/month/year) 20/11/1997
Applicant ISRAEL AIRCRAFT INDUSTRIES LTD. et al.		

This International Search Report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This International Search Report consists of a total of 3 sheets.

☒ It is also accompanied by a copy of each prior art document cited in this report.

1. Basis of the report

a. With regard to the **language**, the international search was carried out on the basis of the international application in the language in which it was filed, unless otherwise indicated under this item.

☐ the international search was carried out on the basis of a translation of the international application furnished to this Authority (Rule 23.1(b)).

b. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international search was carried out on the basis of the sequence listing :

☐ contained in the international application in written form.

☐ filed together with the international application in computer readable form.

☐ furnished subsequently to this Authority in written form.

☐ furnished subsequently to this Authority in computer readable form.

☐ the statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

☐ the statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished

2. ☐ **Certain claims were found unsearchable** (See Box I).

3. ☐ **Unity of invention is lacking** (see Box II).

4. With regard to the **title**,

☒ the text is approved as submitted by the applicant.

☐ the text has been established by this Authority to read as follows:

5. With regard to the **abstract**,

☒ the text is approved as submitted by the applicant.

☐ the text has been established, according to Rule 38.2(b), by this Authority as it appears in Box III. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.

6. The figure of the **drawings** to be published with the abstract is Figure No.

☒ as suggested by the applicant.

☐ because the applicant failed to suggest a figure.

☐ because this figure better characterizes the invention.

7
☐ None of the figures.

INTERNATIONAL SEARCH REPORT

International Application No

/IL 98/00568

A. CLASSIFICATION OF SUBJECT MATTER
IPC 6 G01J5/60

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 6 G01J

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	EP 0 143 282 A (DEUTSCHE FORSCH LUFT RAUMFAHRT) 5 June 1985 see page 5, line 6 - page 19, line 14 see page 22, line 19 - line 20 ---	1-6, 21, 23, 29-32, 45, 46
X	EP 0 420 108 A (EURATOM) 3 April 1991 see the whole document ---	1-6, 8-10, 29, 30
X	US 5 377 126 A (FLIK MARKUS I ET AL) 27 December 1994 see the whole document ---	1-6, 8-11, 29, 30
-/--		

☒ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

* Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search

2 March 1999

Date of mailing of the international search report

12/03/1999

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax: (+31-70) 340-3016

Authorized officer

Ramboer, P

INTERNATIONAL SEARCH REPORT

International Application No

/IL 98/00568

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	GB 2 131 649 A (BRITISH AEROSPACE) 20 June 1984 see the whole document ---	1,12, 50-53
A	WO 97 11340 A (3T TRUE TEMPERATURE TECHNOLOGI ;GLAZMAN EVGENY (IL)) 27 March 1997 see page 8, line 3 - page 9, line 4 see page 9, line 15 - line 38 ---	1,2,5
A	KEALY P S ET AL: "SEPARATING TEMPERATURE AND EMISSIVITY IN THERMAL INFRARED MULTISPECTRAL SCANNER DATA: IMPLICATIONS FOR RECOVERING LAND SURFACE TEMPERATURES" IEEE TRANSACTIONS ON GEOSCIENCE AND REMOTE SENSING, vol. 31, no. 6, 1 November 1993, pages 1155-1164, XP000432082 see the whole document ---	1,2,12, 29,30, 50,51
A	DE 41 34 313 A (DEUTSCHE AEROSPACE) 22 April 1993 see the whole document ---	1,50-53
A	RIICHI NAGURA ET AL: "OPTICAL SENSOR SYSTEM FOR JAPANESE EARTH RESOURCES SATELLITE-1" NEC RESEARCH AND DEVELOPMENT, vol. 33, no. 2, 1 April 1992, pages 226-235, XP000310833 see the whole document ---	1,4,12, 23,29, 45,46,53
A	DATABASE WPI Section EI, Week 8839 Derwent Publications Ltd., London, GB; Class S03, AN 88-277509 XP002095191 & SU 1 383 259 A (AEROGEOLOGIYA) , 23 March 1088 see abstract -----	1,12,13, 25,26, 29,50-53

INTERNATIONAL SEARCH REPORT

Information on patent family members

International Application No

IL 98/00568


Patent document cited in search report		Publication date	Patent family member(s)	Publication date
EP 0143282	A	05-06-1985	DE 3343043 A	05-06-1985
			DE 3414984 A	24-10-1985
			DD 229213 A	30-10-1985
			JP 1796595 C	28-10-1993
			JP 5005051 B	21-01-1993
			JP 60140131 A	25-07-1985
			US 4974182 A	27-11-1990
			DD 229212 A	30-10-1985
EP 0420108	A	03-04-1991	LU 87595 A	07-05-1991
			AT 107021 T	15-06-1994
			AU 639029 B	15-07-1993
			AU 6418590 A	18-04-1991
			CA 2067248 A	26-03-1991
			DE 59006014 D	14-07-1994
			DK 420108 T	29-08-1994
			WO 9104472 A	04-04-1991
			ES 2056328 T	01-10-1994
			IE 64270 B	26-07-1995
			JP 6500387 T	13-01-1994
			PT 95405 A,B	29-05-1992
			RU 2083961 C	10-07-1997
US 5377126	A	27-12-1994	NONE	
GB 2131649	A	20-06-1984	FR 2537289 A	08-06-1984
			SE 8306608 A	02-06-1984
WO 9711340	A	27-03-1997	AU 6888596 A	09-04-1997
			CA 2231166 A	27-03-1997
			CN 1200808 A	02-12-1998
			EP 0848807 A	24-06-1998
DE 4134313	A	22-04-1993	NONE	



INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification ⁶ : G01J 5/60		A1	(11) International Publication Number: WO 99/27336
			(43) International Publication Date: 3 June 1999 (03.06.99)
(21) International Application Number: PCT/IL98/00568		(81) Designated States: AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, DE, DK, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).	
(22) International Filing Date: 20 November 1998 (20.11.98)			
(30) Priority Data: 122258 20 November 1997 (20.11.97) IL			
(71) Applicant (for all designated States except US): ISRAEL AIRCRAFT INDUSTRIES LTD. [IL/IL]; Tamam Division, P.O. Box 75, 56100 Yahud (IL).			
(72) Inventors; and (75) Inventors/Applicants (for US only): KOLTUNOV, Yoseph [IL/IL]; Avivim Street 10/20, 58267 Holon (IL); MAXIMOV, Alexander [IL/IL]; Haarazim Street 17/20, 96181 Jerusalem (IL); MEITIN, Igor [IL/IL]; Ben-Gurion Street 7/30, 54018 Giv'at Shmuel (IL); ALLON, Motti [IL/IL]; Rabinovitz Street 44, 58672 Holon (IL); GUTTMAN, Glen, D. [IL/IL]; Sderot Chen 39, 64166 Tel Aviv (IL); KER-SHENBAUM, Arik [IL/IL]; Moshe Dayan Street 3/1, 43580 Ra'anana (IL).			
(74) Agent: REINHOLD COHN AND PARTNERS; P.O. Box 4060, 61040 Tel Aviv (IL).		Published With international search report.	

(54) Title: DETERMINATION OF TEMPERATURE AND/OR EMISSIVITY FUNCTION OF OBJECTS BY REMOTE SENSING



(57) Abstract

A method and a system for accurate determining temperature and/or emissivity of an object by remote sensing, comprising acquiring electromagnetic radiation data from the object in N spectral bands, deriving temperature and/or emissivity values from said data using a system of equations, each describing the electromagnetic radiation that is emitted from the object in the particular band as a function of temperature and emissivity of the object, wherein the emissivity depends on temperature and wavelength. Based on the above concept of temperature and emissivity determination, there are also developed a method and a system for the object's pattern recognition, being applicable to a number of purposes.

FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav Republic of Macedonia	TM	Turkmenistan
BF	Burkina Faso	GR	Greece			TR	Turkey
BG	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR	Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY	Belarus	IS	Iceland	MW	Malawi	US	United States of America
CA	Canada	IT	Italy	MX	Mexico	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL	Netherlands	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's Republic of Korea	NZ	New Zealand		
CM	Cameroon		Republic of Korea	PL	Poland		
CN	China	KR	Republic of Korea	PT	Portugal		
CU	Cuba	KZ	Kazakstan	RO	Romania		
CZ	Czech Republic	LC	Saint Lucia	RU	Russian Federation		
DE	Germany	LI	Liechtenstein	SD	Sudan		
DK	Denmark	LK	Sri Lanka	SE	Sweden		
EE	Estonia	LR	Liberia	SG	Singapore		

**Determination of temperature and/or emissivity function of objects by
remote sensing**

5

FIELD OF THE INVENTION

The present invention relates to a method and a system for remotely determining temperature and emissivity parameters of objects by multispectral measurements.

10

BACKGROUND OF THE INVENTION

Various approaches have been used, for example, for passive remote sensing of the ground. Thus, maps of surface brightness, temperature and emissivity have been used for investigating geological surface properties (Kahle et al, 1980, Applied Optics, 19, 2279), whereas maps of thermal
15 inertia have been used to infer subsurface properties of soil (Price, 1977, Journal of Geophysical Research, 82, 2582).

The detection of underground structures requires penetration of the ground and is therefore accomplished by active sensing techniques, such as radar (Blake, 1993, "Ground-Penetration Radar Developed by Sweden",
20 International Defense Review, 3, 193; von Maydell et al, 1987, U.S. Patent 4.675,677), or combined passive sensing and radar (Clark et al, SPIE - The International Society for Optical Engineering, 1942, 178).

It is acknowledged in the prior art, that emissivity of various

materials may noticeably depend on wavelength of the emitted radiation and temperature of the sample.

For example, US 4,659,234 describes a method of emissivity error correcting for radiation thermometer, where temperature is determined based on two measurements of radiated infrared energy at two closely adjoining wavelengths, and the result is corrected using one single measurement. While the method is aimed to solve a problem of determining the randomly changing value of emissivity of heated metal objects, it does not take into consideration any dependence of emissivity on the radiation wavelength, and much less - on temperature of the object. Such an approach renders the method inaccurate.

US 5,132,922 describes an emissivity independent multi-wavelength pyrometer operating according to a method using a least-squares-based multiwavelength pyrometry technique and a theoretical function for the dependence of the radiance on the wavelength. However, in this method the emissivity/wavelength function is considered to be the same in all spectral bands, which either leads to a significant reduction in the accuracy of the determined temperature, especially for heated non-transparent materials, or to the use of narrow-band filters. The latter poses a problem for infra-red measurements in real time, since narrow band filters provide insufficient energy for further processing.

Moreover, all the described above methods make an assumption that emissivity of an object is independent of its temperature, since none of the methods appear to suggest any way of considering this dependency for determining temperatures. Such an assumption inadvertently leads to essential errors in the temperature determination for at least non-transparent heated material.

In many branches of industry, for example in metallurgy or in manufacture of semiconductor devices samples and materials are exposed to various operations while being in the heated condition.

Determining temperature of such objects during the manufacturing process presents a very important task, which is rather difficult due to the following factors:

- it is impossible to perform direct temperature measurements, so
- 5 the temperature determining is usually performed via the remotely acquiring data on the infrared radiation of the sample and further processing this data,
- in the mathematical processing of the remotely obtained data many parameters intrinsic to the material of interest must be used (such as its thermal emissivity, etc.), which are usually unknown and cannot be directly
- 10 measured.

Another important task is detection (usually in the dark) and recognition of various objects having different temperatures and/or emissivities. Difficulties of such a process are essentially the same as outlined above.

15

SUMMARY OF THE INVENTION

It is therefore the purpose of the present invention to provide an accurate method of remotely determining temperature and/or emissivity function of objects. It is to be noted, that the problem of determining the

20 emissivity function of real objects is one of important problems in many industrial applications.

Another objective of the invention is designing a system for implementing the above-mentioned method.

Yet another objective of the present invention is to provide a

25 method and a system being capable of detecting and, where applicable, identifying objects on the basis of remotely determined temperature and emissivity distributions.

A specific objective of the present invention will be to provide a

real time recognition of objects (usually in the dark) from a movable platform, using the inventive method.

The term "object" is used herein in a broad sense to denote any kind of structure, crop or articles in a solid, liquid or gaseous state on the ground, natural and artificial underground structure, as well as objects located
5 above the ground (such as solid samples, oil spots on water, clouds, overhead electric wires, etc.).

For the sake of simplicity the term "object detection" will be used in the following description and claims to denote the detection of an object or
10 objects or of some properties thereof.

The above main purpose can be achieved by providing a method of remotely determining temperature of an object, comprising:

- acquiring electromagnetic radiation data from the object in N spectral bands,
- 15 - deriving temperature value from said data using a system of equations, each describing the electromagnetic radiation that is emitted from the object in said band as a function of temperature and emissivity of the object:
the method being characterized in that,
 - said electromagnetic radiation is measured M times, each time in N
20 said spectral bands, thus obtaining $N \cdot M$ readings,
 - a system of $N \cdot M$ equations is formed, each describing the electromagnetic radiation that is emitted from the object in said band as a function of temperature T and emissivity ϵ of the object, wherein the emissivity ϵ is described by a model incorporating at least one function, of at
25 least two arguments being temperature T and wavelength λ : said system comprising $N \cdot M$ readings of the electromagnetic radiation and at least $M+P$ unknowns which include M values of the object's temperature corresponding to said respective M measurements of the electromagnetic radiation and P parameters, wherein $P \geq 2$; said parameters belonging to said model of

emissivity:

- solving said system of $N \cdot M$ equations, thus deriving temperature of the object at any one of the M moments of said electromagnetic radiation measurement, wherein M is a natural number of the set $[1, 2, 3 \dots]$.

5 According to one particular version of the above method, the mentioned model is selected to comprise one function $\varepsilon = f(\lambda, T)$ taking constant values within respective spectral bands, and therefore P is considered equal to N ,

thereby said system of $N \cdot M$ equations is formed to comprise $N \cdot M$ readings
10 of the electromagnetic radiation and $N + M$ unknowns which include M values of the object's temperature corresponding to said respective M measurements of the electromagnetic radiation, and N values of emissivity for said respective N spectral bands.

The above-defined particular method is based on the following
15 assumptions:

1. Emissivity of the object in each one of the N spectral bands is a predetermined function of temperature having parameters which are constant during all the M measurements of the electromagnetic radiation performed in this band.
- 20 2. During each specific measurement of the electromagnetic radiation, temperature of the sample is assumed to be constant (i.e. its change is considered negligible), regardless the spectral band where such specific measurement is performed.

The assumption 2 is best fulfilled if each measurement of the
25 electromagnetic radiation is performed in all N spectral bands substantially simultaneously. It is especially important for accurate measurements concerning objects which undergo either heating or cooling. For an object or a plurality of objects which have rather constant or slowly changing temperatures, the measurements in N spectral bands may be accomplished in

sequence, at a maximally available speed.

In practice, i.e. when digital computing technology is used for controlling the process of measurements and processing the obtained data, each of said M multispectral measurements of the electromagnetic radiation
5 (i.e. each of said M*N readings thereof) is digitized and stored in a computer memory for further computerized processing, said processing comprising substituting the digitized M*N readings of the electromagnetic radiation into said M*N equations, and solving thereof.

Preferably, the above measurements are to be provided in the
10 infrared spectrum.

According to one specific version of the method said equations are integral ones, for example Fredholm equations relating to emissivity.

It should be emphasized, that the above-defined method easily provides sufficiently accurate temperature values both in cases when
15 emissivity of the object essentially varies from one spectral band to another (either due to dispersion between these bands, or due to specific physical properties of the object), and in cases when the emissivity is rather uniform throughout the spectrum.

In addition, a succession of temperature values obtained by the
20 method can be used for real-time monitoring and controlling of the object's thermal condition, for example during a technological process to which the object is subjected.

It is well known, that at high temperatures (i.e. those between the room temperature and 1,500⁰C) emissivity of some real materials, such as
25 semiconductor samples, varies not only from one spectral band to another, but also depends on the temperature of the sample. One of the reasons for such an effect is degrading of the sample's transparency with the temperature increase, that consequently affects emissivity of the sample. In other words, the simplest case of assumption I mentioned above is not applicable to such

objects. and. when temperature of heated non-transparent objects must be determined. the method where only $N+M$ unknowns are sought for will not be sufficiently accurate. It means, that if the sample emissivity is considered to be independent from temperature while the sample undergoes any thermal
5 treatment, this assumption will be a source of essential errors in calculations of the temperature.

Having assumed, that emissivity of the heated sample is a known mathematical function of temperature and wavelength with unknown parameters. the inventors suggested to introduce such parameters as
10 unknowns into the above-mentioned system of equations. in order to obtain values of the parameters by solving the system.

More particularly, each of said $M*N$ equations describes the electromagnetic radiation that is emitted from the object in one of said bands as a function of the temperature and the respective emissivity of the object,
15 the emissivity, in turn, being a known function of temperature, wavelength and a known number of unknown parameters; said parameters being introduced as additional unknowns into said system of equations for further obtaining their values upon solving the system.

In one example, the mentioned known function may be
20 represented as a sum of a known number of terms of two other functions. a first of which being dependent only on temperature and a known number of unknown parameters, and a second - only on wavelength and another known number of other unknown parameters.

According to another example, this known function may be
25 represented by a polynomial expansion having K unknown coefficients. said coefficients being introduced into the system of equations as unknown parameters to be determined among said unknowns upon solving said system.

If the emissivity variable in each of the above mentioned equations is represented as a polynomial function having K unknown coefficients. the

system of the equations will overcome some transformations. Namely, though the number of equations $N \cdot M$ is unchanged, the number of unknowns in the system will increase and become equal to $M + K \cdot N$, where K is the number of polynomial coefficients of the function emissivity/temperature in each of the N spectral bands. However, if the numbers of the polynomial coefficients are different in different spectral bands (which case is more general and more correct from the physical point of view), the number of unknowns in the system will be $M + (K_{\Delta 1} + K_{\Delta 2} \dots + K_{\Delta N})$,

where $K_{\Delta 1} \dots K_{\Delta N}$ are numbers of the polynomial coefficients of the emissivity/temperature function in each of the spectral bands, respectively.

In practical applications, where the electromagnetic measurements are performed and processed by the aid of computer, the number of electromagnetic radiation measurements M and the number of spectral bands N may be as great as is wished. For example, in industrial conditions during a relevant technological process up to 2,000 measurements may be performed in a short period of time, each measurement taking from 1 to 10 msec. On the other hand, the number K of polynomials in the function emissivity/temperature usually does not exceed 4. Owing to that the system of such equations is solvable, since

$$N \cdot M \gg M + K \cdot N, \text{ or}$$

$$N \cdot M \gg M + (K_{\Delta 1} + K_{\Delta 2} \dots + K_{\Delta N}).$$

The most effective application of the above described modified method is for non-contact temperature measurement of heated non-transparent objects, for example of semiconductor materials and samples during their manufacture.

It should be emphasized, that, since values (parameters) of the emissivity function are solutions of said system of $M \cdot N$ equations, as well as the temperature values are, the disclosed above method of remotely measuring temperature of an object constitutes also a method of determining

the emissivity function of the object.

In other words, there is provided a method of remotely determining emissivity function of an object, comprising

- acquiring electromagnetic radiation data from the object in N spectral
5 bands in the infrared spectrum by measuring it M times, each time in N said spectral bands, thus obtaining N*M readings,
- forming a system of N*M equations, each describing the electromagnetic radiation that is emitted from the object in one of said bands as a function of temperature T and emissivity ε of the object, wherein the
10 emissivity ε is described by a model incorporating at least one function, of at least two arguments being temperature T and wavelength λ ; said system comprising N*M readings of the electromagnetic radiation and at least M+P unknowns including M values of the object's temperature corresponding to said respective M measurements of the electromagnetic radiation, and P
15 parameters, wherein $P \geq 2$; said parameters belonging to said model of the emissivity:
- solving said system of N*M equations to derive said P parameters, thereby reconstructing the emissivity function of the object.

All the above-described modifications of the method for
20 determining temperature are applicable to the method for determining emissivity, *mutatis mutandis*.

It should be appreciated, that the above described methods for remotely determining temperature and/or emissivity function of an object may be utilized for deriving temperature and/or emissivity descriptive maps of the
25 object.

To the above-mentioned purpose, the object is to be divided into a plurality of representative segments, and each segment is to be investigated according to the above-suggested technique. The processed data on the temperature and/or emissivity function associated with each specific segment

of the object can then be used for forming a corresponding pixel of the respective descriptive map.

As has been mentioned earlier, "the object" is defined in a broad sense, so it can be understood as a plurality of so-called sub-objects having
5 different temperatures and/or emissivities and dislocated in a selected region which limits the object in space (for example, the sub-objects being such as the ground, the space above including one or more articles, the surrounding atmosphere in the selected region). Consequently, when the object is divided
into a plurality of representative segments, in most cases the sub-objects will
10 not coincide with the representative segments, for example one sub-object may be covered by a number of segments and should be thereby represented by a number of corresponding pixels.

Further, the above-described method can serve for the object detection on a background of the ground and/or the surrounding atmosphere
15 in a selected region. For this purpose, the method may additionally comprise the following steps:

- acquiring meteorological data indicative of climatic conditions of the selected region on the ground and/or the surrounding atmosphere;
- recording the acquired electromagnetic radiation and meteorological
20 data by means of suitable data recording means;
- storing the so-recorded data in suitable data storage means and deriving from the so-stored data, descriptive maps of the selected region; and
- feeding data of said descriptive maps into pattern recognition
25 processor means to classify the pixels of said maps of said selected region, whereby the desired object detection is achieved.

By one embodiment of the invention said meteorological data are obtained from meteorological stations.

Typically the said descriptive maps are temperature, emissivity and

albedo maps. Albedo is a parameter which can be defined as follows:

$$A = \frac{R_v}{\tau_v \tau_o W_s}$$

where, R_v is the radiation measured by the radiometer in the visible and near
5 infra red regions; τ_v , is the atmospheric transmissivity in the visible and near
infra red regions; τ_o , is the optical transmissivity of the radiometer including
the transmissivity of the spectral filter in the visible and near infra red regions;
and W_s is the radiation from the sky.

According to one embodiment of the invention applicable in cases
10 where the objects detection is based on pronounced temperature and/or
emissivity differential between the representative segments of the object. the
object detection according to the invention is based on a single scanning pass
of the selected region (i.e. M=1). This embodiment of the invention may be
applicable, for example, to the detection of overhead high voltage wires,
15 defects in the wires, connectors and insulators, or diseases in crops. In the
performance of this embodiment, the descriptive maps describe temperature
and emissivity and the pattern recognition processor means classifies the
pixels according to temperature and/or emissivity difference. Typically, the
emissivity map is used by the pattern recognition means in the classification
20 process. In the case of overhead high voltage systems for example, any such
local temperature increase denotes a possible defect in the inquiry sector
thereof.

If desired, the emissivity map can be used to remove background
noise, hence enhancing the temperature differences of the object under
25 investigation. This is done by using the emissivity map to identify those
pixels belonging to the object under investigation. Any temperature
differences belonging to the background are then eliminated.

According to another embodiment of the invention the object detection is based on multiple scanning passes at desired times ($M=2, 3, 4, \dots$) and said descriptive maps describe temperature, emissivity and albedo, wherefrom a set of characteristic maps of the selected region are derived by
5 incorporating suitable reference data.

Typically an optimal set of characteristic maps of the selected region is chosen and data thereof are fed into the pattern recognition processor means in order to classify the pixels of said optimal set of characteristic maps of the selected region, whereby the desired object
10 detection is achieved. The set of characteristic maps may comprise maps of thermal inertia, thermal flux, coefficient of heat transfer and coefficient of mass transfer.

The scanning of the selected region for measuring electromagnetic radiation in a number of spectral bands may be effected either by remote
15 scanning or by close range scanning.

In general, the pattern recognition processor means first defines the number of classes that the selected region is to be divided into. It then divides the selected region into the defined number of classes by statistically associating each pixel of the characteristic maps with a given class. Although
20 the classes are not necessarily identified with areas having different physical properties, e.g., areas of water, rocks, vegetation, sand, soil, etc., there should be some correlation between the two for the process of associating the pixels to each class to be successful. For a given selected region there exist preliminarily determined universal reference data that are required in order to
25 evaluate the characteristic maps. The values of the reference data are obtained in controlled experiments as described below. It has been found that sufficient accuracy can be obtained in the detection process by using an average set of universal constants. This set is derived by taking the average value of the set obtained for ground relative humidities less than 12% and that obtained for

ground relative humidities greater or equal to 12%. The term "universal reference data" indicates that, to a good approximation, the reference data are suitable for all kinds of backgrounds and objects. In the advent that greater accuracy, with respect to the ground humidity, is desired in the detection
5 process, the universal sets from which the average set was derived can be used, depending on the humidity of the ground.

When the object detection according to the invention aims at detecting below ground level characteristics of the selected region, e.g. at finding underground artificial structures, geological structures holding
10 deposited minerals, etc., the underground structure of interest will then show up as an anomalous pattern in the pattern recognition process, due to the fact that the heating and cooling processes of the ground are different in the region of the underground structure as compared to the surrounding region which is absent of such underground structures. In other words, the pattern recognition
15 means will not be able to associate those pixels identified with the underground structure with one of the defined classes.

In general then, object detection entails pixel classification, in which a number of classes is defined and the pixels in the selected region are statistically associated with the classes. To this end a quality function is
20 defined and the pattern recognition process entails determining that set of characteristic maps that maximizes the quality function. Anomalous patterns are those in which the pixels cannot be associated with a given class in the selected region. Where possible, it is preferable that the pixel classes correspond to areas having well known physical properties.

25 Although the reference data can be considered as universal, more accurate values can be used if desired. Values for the reference data for different backgrounds or objects can be obtained by measuring the radiation from a reference sample of known emissivity, of the background or object of interest, at predetermined times and at the same time directly measuring the

temperature thereof. The reference data can then be derived from the measured data by utilizing an energy balance equation.

By one embodiment of the invention the remote scanning of the selected ground region is performed with at least five sensors operating, respectively, in the 3-4 μ , 4-5 μ , 8-10 μ , 10-12 μ and the near infrared and visible spectral bands, and there is provided at least one further sensor for measuring electromagnetic radiation from the space above, operating in the 0.4-2 μ spectral band.

Quite generally, the characteristic maps of the selected region include maps of thermal inertia, thermal conduction flux, coefficient of heat transfer, coefficient of mass transfer, and the mean, variance and texture maps derived therefrom. However, if the relative humidity of the ground in the scanned region is greater than 30%, these maps cannot be computed.

Preferably, the said classifying processor means in which the pixels of the characteristic maps of the selected region are classified into classes, makes use of a poly-Gauss expansion to describe the statistical distribution of the pixels and Bayes' method to sort the pixels into classes.

For the said evaluation of the sets of characteristic maps for the purpose of selecting therefrom an optimal set, the said pattern recognition means comprises quality factor evaluation means and the pattern recognition process entails determining a set of characteristic maps for which the quality factor is the highest, thereby giving rise to the best pixel classification.

The pattern recognition means can also include additional geometrical classification means for determining the shape of the detected object.

Still further, the method can be specifically adapted for real time temperature/emissivity mapping of a plurality of selected regions to be observed, in said method the step of acquiring said electromagnetic radiation data is provided in real time by equipment mounted on a movable platform,

while displacing along said plurality of selected regions; wherein the steps of recording and storing the acquired electromagnetic radiation and meteorological data and further deriving from the so-stored data, descriptive maps of the selected region are registered (i.e. aligned) with the platform displacement.

5 It is understood, that the above method may include automatic recognition of objects positioned along or on the course of the moving platform, such as a vehicle. Still further, the method may comprise steps of initiating an alarm and, optionally, of automatic adjusting the course of the vehicle whenever an obstacle is recognized.

10 In accordance with a further aspect of the invention, there is provided a system for remotely determining temperature and/or emissivity function of an object, said system comprising:

scanning means for acquiring electromagnetic radiation data from
15 the object M times, each time in N spectral bands, thus obtaining N*M readings of the electromagnetic radiation, wherein M is a natural number of the set [1, 2, 3 ...];

means for recording and storage said N*M readings in the digital form;

20 computational means for processing said N*M readings of the electromagnetic radiation as a system of N*M equations comprising M unknown values of temperature and at least P unknown parameters, wherein $P \geq 2$; said parameters belonging to a model of the objects emissivity, the model comprising at least one function of at least two arguments being
25 temperature T and wavelength λ ;

display means for displaying one or more of said unknowns obtained upon solving said system of equations, or derivatives therefrom.

The above system for remotely determining temperature and/or emissivity function of an object can serve for deriving temperature and/or

emissivity descriptive maps of the object, if said scanning means are capable of acquiring the electromagnetic radiation from a plurality of representative segments of the object, and said computational means are capable of processing the acquired data, for deriving and displaying the temperature
5 and/or emissivity descriptive maps of the object by the display means.

The scanning means may comprise a plurality of sensors capable of simultaneously measuring electromagnetic radiation in a number of spectral bands.

In another embodiment, the scanning means may comprise a
10 spatial optical filter divided into a number of sites for simultaneous acquiring the electromagnetic radiation from said plurality of respectively located segments of the object; each said site having N zones responsible for splitting the radiation acquired by the site into N spectral bands, thereby acquiring the electromagnetic radiation in all N spectral bands simultaneously. The splitting
15 can be provided by chromatic beam splitters.

According to an alternative embodiment of the invention, the scanning means comprise a rotatable optical filter for acquiring electromagnetic radiation in said N spectral bands in sequence, and at least one infrared sensor.

20 If desired, said sensors are capable of remote scanning. Alternatively, the sensors may be designed for close range scanning.

By another embodiment of the invention the scanning means comprises at least five ground oriented sensors operating, respectively, in the 3-4 μ , 4-5 μ , 8-10 μ , 10-12 μ and the near infrared and visible spectral bands
25 and at least one space oriented sensor operating in the 0.4-2 μ spectral band.

In the preferred embodiment, the system is capable of object detecting in a selected region having a background including the ground and/or the surrounding atmosphere, further comprising:

- means for acquiring meteorological data indicative of climatic

conditions of the selected region and the surroundings;

- means for recording said meteorological data;
- data storage means for storing the recorded meteorological data (possibly the same means as for storing the electromagnetic radiation data);
- 5 - computational means for deriving from the stored meteorological data and the data on the electromagnetic radiation, descriptive maps of the selected region; and
- pattern recognition processor means for classifying the pixels of said maps.

10 By one embodiment of the invention said means for acquiring meteorological data are associated with meteorological stations.

In accordance with a preferred embodiment of the invention said computational means are capable of deriving from said descriptive maps a set of characteristic maps. In such an embodiment the said processor means
15 preferably comprise optimizing means for selecting an optimal set of characteristic maps which is subjected to pixel classification. The pattern recognition processor means can comprise pixel classification means in which a number of classes is defined whereby the classified pixels are statistically associated with the classes. For example, the pattern recognition processor
20 means can function based on a poly-Gauss expansion for determining the statistical distribution of the pixels, and means based on Bayes's method for sorting pixels into classes. The pattern recognition processor means may also comprise quality factor evaluation means.

According to one specific embodiment of the invention, the
25 pattern recognition processor means includes additional geometrical classification means for determining the shape of the detected object.

In a specific embodiment of the invention, the remote sensing equipment and the data recording means are positioned on any movable platform (for example, are airborne), whereas the data storage means,

computational means, classification means and pattern recognition means are on the ground. Alternatively, in some embodiments the remote sensing equipment, data recording means, data storage means, computational means, classification means and pattern recognition means may all be positioned on a
5 movable platform (or, in a particular case, be airborne).

In the above embodiments, said computational means are adapted to stabilize and register the recorded and stored data of the acquired electromagnetic radiation with the platform's movement to obtain a real time mapping and pattern recognition.

10 It should be appreciated, that pattern recognition processor means can be capable of automatic recognition of objects positioned along or on the course of the moving platform, and if necessary, of initiating an alarm and automatic adjusting the course of the vehicle whenever an obstacle is recognized.

15 It goes without saying, that in the embodiments where the system enables the descriptive maps and the pattern recognition to be accomplished, the display means are capable of displaying the appropriate output data.

BRIEF DESCRIPTION OF THE DRAWINGS:

20 In order to understand the invention and to see how it may be carried out in practice, a preferred embodiment will now be described, by way of non-limiting example only, with reference to the accompanying drawings, in which:

Figs. 1a and 1b present a flow-chart of the algorithm illustrating a
25 method of non-contact temperature measurement according to the invention.

Fig. 2 is a flow-chart of a modified method based on that illustrated in **Fig. 1b**.

Fig. 3 is a block-diagram of a system implementing the inventive

method.

Figs. 4a and 4b are schematic plan views of two embodiments of the filter shown in Fig. 3.

Fig. 5 is a block diagram of the process for determining the characteristic maps of the region selected for scanning.

Fig. 6 is a block diagram of the pattern recognition process.

Fig. 7 is a block diagram of a system according to the invention for performing non-contact temperature/emissivity measurements and pattern recognition.

10 DETAILED DESCRIPTION OF PREFERRED EMBODIMENTS

Before relating to the drawings, some basic terms and indications of constants and variables are to be introduced, which will be used further below in the examples of the inventive method.

In the case, when the method is applied to detecting and recognizing objects on or above the Earth's surface, a multi-spectral scanning means (e.g. radiometer) scans the area of the surface under investigation at, at least one pixel at a time. The radiation received from each pixel by the radiometer, and by a pyranometer which receives radiation from the sky, serves as input for processing means which computes descriptive and characteristic maps of the selected region. The processing software is based on the Planck's equation:

$$W = \int \tau_a(\lambda) \tau_o(\lambda) \varepsilon(\lambda, T) B(\lambda, T) d\lambda + \int \tau_a(\lambda) \tau_o(\lambda) (1 - \varepsilon(\lambda, T)) J(\lambda, T_s) d\lambda \quad (1)$$

where the integral is over the spectral region of the sensor under consideration and where:

W is the radiation received by the radiometer,

$\tau_a(\lambda)$ is the spectral atmospheric transmissivity which can be obtained from

standard sources (Wolfe and Zissis, Editors, 1993. The Infrared Handbook - revised edition. Environmental Research Institute of Michigan. U.S.A.; Selby et al, 1978. Atmospheric Transmittance/Radiance: Computer Code LOWTRAN 4, report no. AFGL-TR-78-0053. Optical Physics Division, Project 7670. Air Force Geophysics Laboratory, Hanscom AFB, MA. USA),
 $\tau_o(\lambda)$ is the spectral optical transmissivity of the radiometer including the transmissivity of the spectral filter, which can be measured by standard methods.

$\varepsilon(\lambda, T)$ is the emissivity of a pixel in the selected region,

10 T is the temperature of a pixel in the selected region,

$B(\lambda, T)$ is the spectral radiance of a black body at surface temperature T , (for the definition of $B(\lambda, T)$ see - Bramson, 1968. Infrared Radiation - A Handbook for Applications. Plenum Press)

T_s is the sky temperature, and

15 $J(\lambda, T_s)$ is the sky spectral radiance which is given by $B(\lambda, T_s)$, where a possible choice for T_s is $T_s = T_a - 10^\circ K$, and where T_a is the temperature of the atmosphere in the vicinity of the selected region.

The method will be further explained for a simplified particular
 20 example. e.g. for an object consisting of materials homogenous from the point of view of radiation parameters.

Radiation of the object includes three components:

$$W = W1 + W2 + W3$$

$$W1 = \varepsilon * W_B$$

25 $W2 = R * Y$

$$W3 = tr * G$$

where:

W - total radiation of the object received by the radiometer

$W1$ - radiation emitted by the object

$W2$ - radiation reflected by the object

$W3$ - radiation transmitted by the object through its body

ε - emissivity coefficient of the object

R - reflectance coefficient

5 tr - transmittance coefficient

$$(I = tr + R + \varepsilon)$$

W_B - radiation of the black body having temperature equal to that of the object

G - radiation existing at the back side of the object

10 Y - background radiation arriving to the object.

For a non-transparent object (having $tr = 0$), which is heated to a relatively high temperature with respect to the ambient one, both $W2$ and $W3$ are equal 0.

In this case radiation W^i in the spectral band $\Delta_i = [\lambda_i, \lambda_i^1]$ can be
15 represented by a formula (2) derived from the general (Planck's) equation (1):

$$W'' = \int_{\lambda_i}^{\lambda_i^1} \varepsilon(\lambda, T) * B(\lambda, T) * d\lambda \quad (2)$$

i.e. taking into consideration that τ_A and τ_0 are equal 1 and all members concerning atmosphere and sky are suppressed.

For determining intensity of infrared radiation emitted from the object, a
20 reference body can be selected, for which there are known its radiation/temperature dependencies in each predetermined spectral band.

A radiometer can detect radiation of the object in several spectral bands. In a specific spectral band, the received radiation V^i may be represented by a Fredholm equation (3):

$$I'' = \int_{\lambda_i}^{\lambda_i^1} \varphi'(\lambda) * \varepsilon(\lambda, T) * B(\lambda, T) * d\lambda \quad (3)$$

where

$\varphi^i(\lambda)$ - function dependent on the radiometer's parameters for specific band "i" and on transmitting properties of the atmosphere.

If the radiation measurements are performed M times (1...j...M), and
5 each time in N spectral bands (1...i...N), simultaneously (see blocks 1. 2. 3 in Fig. 1a). the following system of (N*M) equations may be built and solved:

$$I'' \equiv V''_T = \int_{\lambda_i}^{\lambda_j} \varphi^i(\lambda) * \varepsilon(\lambda, T_j) * B(\lambda, T_j) * d\lambda \quad (4)$$

Solution of the above system of equations will comprise M values of temperature ($T_1..T_j..T_M$) and, (in this simplified case), N values of
10 emissivities ($\varepsilon_1... \varepsilon_i... \varepsilon_N$) as can be seen from both the equations (4) and Figs 1a, 1b (blocks 4, 5, and 6).

Fig. 2 illustrates another final portion of the flow-chart. which, together with the flow-chart diagram shown in Fig. 1a will form a general algorithm for cases when the object's emissivity depends both on wavelength
15 and temperature. The system of equations processed in block 7 of the general algorithm is more complex than system (4) (see also block 5 in Fig. 1b), namely: in each of the N*M equations dependence of the emissivity variable " ε " from temperature of the sample is taken into consideration.

For example, emissivity function of the heated object in spectral
20 channel "i" can be represented as follows:

$$\varepsilon^i(\lambda, T) = \sum_{k=1}^K E_k^i(\lambda) * S_k^i(T) \quad (5)$$

$(\lambda \in \Delta_i)$

where: $S_k^i(T)$ - is a function reflecting dependency of the emissivity on temperature;

$E_k^i(\lambda)$ - is a function reflecting dependency of the emissivity on
25 wavelength.

K - is the preselected number of terms $S_k^i(T) * E_k^i(\lambda)$

Behavior of the functions $S_k^i(T)$ and is assumed to be known (i.e. the functions are selected in advance); parameters of the function $E_k^i(\lambda)$ are also assumed to be known.

Based on the above, the following system of $N \times M$ equations may be
5 built and solved:

$$I^{''} = \sum_{k=1}^K S_k^i(T_j) * R_k^i(T_j) \quad (6)$$

where:

$$R_k^i(T) = \int_{\lambda_i}^{\lambda_f} E_k^i(\lambda) * \varphi^i(\lambda) * B(\lambda, T_j) * d\lambda \quad (7)$$

is integral of the preselected functions E , B and φ .

Solving the system (6) permits derivation of M values of the sample
10 temperature, and $N \times K$ parameters for each of the functions $S_k^i(T_j)$.

In yet another example, the above mentioned emissivity function $S_k^i(T_j)$ may be expanded into a polynomial series, and the equation (5) will acquire the following form:

$$\varepsilon(\lambda, T) = \sum_{k=1}^K \sum_{q=1}^Q b_{kq}^i * P_q^i(T_j) * E_k^i(\lambda) \quad (8)$$

$(\lambda \in \Delta_i)$

15 where:

b_{kq}^i = parameters of function $S_k^i(T_j)$ in the "i" spectral band;

$P_q^i(T_j)$ = polynomial of a pre-selected form and with pre-selected coefficients;

$(b_{kq}^i * P_q^i(T_j))$ forms $S_k^i(T_j)$;

20 Q - number of polynomial coefficients.

The system of equations in this case will be as follows:

$$I^{''} = \sum_{k=1}^K \sum_{q=1}^Q b_{kq}^i * P_q^i(T_j) * R_k^i(T_j) \quad (9)$$

where:

$$i = \{1, N\}, j = \{1, M\}, k = \{1, K\}, q = \{1, Q\}.$$

Solution of the above system of $N \cdot M$ equations will give M unknown values of temperature, and $N \cdot K \cdot Q$ parameters b_{kq}^i of the function $S_k^i(T_j)$ (for the case when in each spectral band there is one and the same number of the
 5 parameters).

It should be emphasized that, knowing the above mentioned parameters and the functions $E_k^i(\lambda)$, one can exactly define the wavelength and temperature dependent function of emissivity.

The above system of equations is linear for parameters b_{kq}^i , and
 10 non-linear for values of temperature T_j .

Accuracy of the temperature calculations depends on the following parameters:

- number N of the spectral bands, and on specific selection of the bands.
- 15 - number M of the "temperature" (i.e. electromagnetic radiation) measurements,
- quality of synchronizing of the "temperature" measurements in the N spectral bands. i.e. performing thereof (in the best case) substantially simultaneously,
- 20 - technical parameters of radiometers and accuracy of the radiometric measurements,
- accuracy of the mathematical model.

Based on the above description and examples, the method of remotely measuring temperature of an object suggested in the present application
 25 represents also a method of determining emissivity function of the object.

Fig. 3 illustrates a block-diagram of a system capable for implementing the inventive method. An object 10 (for example, a heated object) emits infrared radiation on to an optics 12 via which it is transmitted to a multichannel spatial filter 14. The multichannel spatial filter 14 performs

simultaneous splitting of spectral lines into N spectral bands. In Fig. 4a there is shown a schematic plan view 28 of the multichannel spatial filter which is designed to split the spectrum into $N=12$ spectral bands (channels) by 12 zones capable to transmit radiation of different wavelengths. Practical
5 implementation of the filter is not discussed in the frame of the present patent application. Intensities of the obtained N radiation portions are then detected by a detector 16 adapted for multichannel detection. " N " analogous readings of the electromagnetic radiation obtained by the detector 16 are converted into the digital form and transmitted to a processing unit 18 where they are stored
10 for further processing.

All the above-described operations are synchronized by a control unit 20 of the processing unit 18, which generates M successive synchronizing signals. Each of these M signals simultaneously activates optics 12, multichannel filter 14, detector 16 and processing unit 18 for performing and
15 recording one of the M measurements of the infrared radiation being effected simultaneously in N spectral bands. $M*N$ obtained digitized readings of the infrared radiation emitted from the object 10 are processed in the unit 18 as a system of equations having at least $M+P$ unknowns comprising M values of temperature of the object and at least P parameters of its emissivity model.
20 Values of the temperature (and/or of the emissivity), being solutions of these equations, are displayed by a display 22. If desired, the system can be adapted for deriving a temperature descriptive map of the object, as well an emissivity descriptive map thereof. To this end, optional thermal mapping unit 24 and an emissivity mapping unit are connected to the processing unit 18. Fig. 4b
25 shows a filter structure suitable for making the mapping operation.

Fig. 4b illustrates a plan view of a spatial filter 30 divided into a number of sites 32 for acquiring infrared radiation from a number of respectively located segments of the object (not shown). Each site has $N=4$ zones responsible for splitting the infrared radiation acquired by the site into

four spectral bands. Plurality of the split radiation portions from all sites of the filter 30 may be then transmitted to a detector similar to that shown as 16 in Fig. 3, and further to a similar processing unit. The processing unit will process the stored digitized information so as to produce values of
5 temperature and/or emissivity associated with every one of the sites 32 of the filter 30, for further composing a descriptive map of temperatures (emissivities) of the corresponding segments of the object.

Geometric shape and parameters of the spatial filter 30 may be selected according to each specific application.

10 **Figs. 5 and 6** schematically illustrate a particular example of the inventive method for obtaining temperature/emissivity maps of a selected region, with providing of further pattern recognition based on the obtained data. The particular example described below focuses on the detection of underground structures. It should be noted, however, that it applies mutatis
15 mutandis to the detection of on ground as well as to above ground targets.

Typically, the system used for passive remote sensing of the Earth's surface is a multi-spectral radiometer designed to operate in some convenient atmospheric window, e.g., between 8 and 12 μ . The configurations and operation of such systems is well known to those skilled in the art
20 (see, e.g., various articles appearing in: Proceedings of the First International Airborne Remote Sensing Conference and Exhibition, 12-15 September, 1994, Strasbourg, France) and, therefore, will not be expounded upon herein. Similarly, the operation of pyranometers, for measuring optical radiation from the sky, is well known to those skilled in the art (Kondratyev, 1969, Radiation
25 in the Atmosphere, 62, Academic Press) and, will also not be expounded upon herein.

The detection of underground structures is performed by scanning the area of the Earth's surface under investigation a number of times, and extracting from the recorded data physical information characterizing heating

and cooling processes that take place not only at the Earth's surface but also below the Earth's surface. To this purpose an equation of thermal balance is used that contains information regarding heat transfer processes above and below the Earth's surface, through a set of thermophysical constants. The information obtained is then processed by suitable statistical methods in order to detect regions having different thermal properties, in the region selected for scanning. These thermophysical inhomogeneous regions are classified in a pattern recognition process in which the underground structures are identified.

The detection process is divided into two main stages: a pre-processing stage, in which temperature, emissivity and characteristic maps (maps of the thermophysical constants and statistical derivatives thereof) of the selected region are produced and a pattern recognition stage in which the underground structures are detected.

To effect the pre-processing stage a multi-spectral radiometer scans the area of the Earth's surface under investigation at, at least one pixel at a time. The radiation received from each pixel by the radiometer, and by the pyranometer which receives radiation from the sky, serves as input for pre-processing software which computes characteristic maps of the selected region based on the Planck's equation, the albedo equation and the energy balance equation.

A series of scans of the selected region are performed during a twenty-four hour period and the thermophysical constants are extracted from the energy balance equation (10):

$$\begin{aligned}
 (T(t) - T_0) P &= \frac{I}{\sqrt{\pi}} \int_0^1 \frac{I}{\sqrt{1-\eta}} [(1-A)] d\eta \\
 &- \frac{\alpha}{\sqrt{\pi}} \int_0^1 \frac{I}{\sqrt{1-\eta}} f(V(\eta), T_a(\eta) - T(\eta)) d\eta \\
 &- \frac{\beta}{\sqrt{\pi}} \int_0^1 \frac{I}{\sqrt{1-\eta}} g(\eta) d\eta
 \end{aligned}$$

$$+ \frac{Q}{\sqrt{\pi}} \int_{t_0}^t \frac{1}{\sqrt{t-\eta}} d\eta \quad (10)$$

where. $T(\eta)$ is the temperature of a pixel in the selected region at time η , T_0 is the temperature of the pixel at the time, t_0 , of the first scan of the series, $T_a(\eta)$ is the temperature of the atmosphere in the vicinity of the selected
 5 region at time η , $I(\eta)$ is the radiance of the sun and the sky in the visible and near infra red region, $J(\eta)$ is the radiance of the sky and the sun in the region 8 - 12 μ at time η ,

σ is Stefan Boltzman's constant,

P is the thermal inertia.

10 α is the coefficient of heat transfer,

β is the coefficient of mass transfer, and

Q is the thermal flux for conduction.

The energy balance equation (10) contains two functions. f and g that will be described below, and four unknown thermophysical constants,
 15 α β P and Q that are to be computed at each pixel. Since, in the example chosen, of an underground structure, there are four unknowns, four equations are required to solve for them. The four equations are obtained by scanning the selected region five times during a twenty-four hour period. The first scan, performed at time $t=0$ gives rise to zero on the left hand side of equation (10)
 20 and is not used. The remaining four scans give rise to a set of four linear equations which can be solved for the unknown thermophysical constants. Since the computations are performed for each pixel of the selected region the result is a set of maps, an α map, a β map, a P map and a Q map.

As is well known to those skilled in the art, there are a number of
 25 possibilities for the choice of the function f for a discussion of various possible choices see: Jakob. 1965. Heat Transfer. John Wiley & Sons. For example, for low wind speeds an expression for this function is given on page 473. Eqn. (22-91), whereas for high wind speeds an appropriate expression is

given on page 555 by Eqn. (26-29)). In the present example, the following choice for the function f is made:

$$f = (0.064 + 0.032 V(\eta)^{0.8}) (T_a(\eta) - T(\eta))$$

where, $V(\eta)$ is the wind speed over the selected region at time $t = \eta$ and the other variables are as defined above. This expression for the function f is valid for wind speeds less than 40 kilometers per hour.

There are also a number of possibilities for the choice of the function g (see Rosema, 1975, "Simulation of the Thermal Behavior of Bare Soils for Remote Sensing Purposes" in: Report 11. Netherlands Interdepartmental Working Community for the Application of Remote Sensing Technology, Delft, The Netherlands), in the present example the following choice is made:

$$g(\eta) = (\eta - t_a)^{\gamma_1} e^{\gamma_2 (\eta - t_a)}$$

where, t_a is the time at which water starts to evaporate from the ground, at the selected region, due to heating by the sun. This time is normally defined as the time at which the sun makes an angle of 20° to the horizon during sunrise. γ_1 and γ_2 are constants that are determined empirically by performing controlled measurements for given families of ground types. Once determined, the values of γ_1 and γ_2 can be stored and used as required. In general the values of γ_1 and γ_2 depend on the humidity of the ground. It has been found that they have one substantially constant value, for relative humidities less than 12%, and another substantially constant value for relative humidities greater or equal than 12% and less than 30%. For example, for sand-based earth $\gamma_1 = 4.76$ and $\gamma_2 = 0.72$ for relative humidities of the ground less than 12%, and $\gamma_1 = 4.61$ and $\gamma_2 = 0.748$ for relative humidities of the ground greater or equal than 12%. Detection of underground structures for relative humidities of the ground above 30% and for rainy conditions is not possible. Information on rain, clouds, the atmospheric temperature and wind speed is obtained from meteorological stations.

The computation of the thermophysical constants is summarized in Fig. 5. The radiation measured by the multi-spectral radiometer (block 41) along with relative humidity and atmospheric temperature readings (block 42) is conveyed to the computational process (block 43) which uses the
 5 above-described equation (4) and an albedo equation to compute the temperature (T), emissivity (ε) and albedo (A) maps, which are stored in the storage means (block 44). After the fifth scan in the twenty four hour period has been made, the T, ε and A maps from the last four scans along with the time t_n and the wind speed V are conveyed to the computational process
 10 (block 45), which uses the energy balance equation, to compute the maps of the thermophysical constants α , β , P and Q.

The pattern recognition stage is initiated by a process in which an optimal set of characteristic maps is determined. In addition to the α , β , P and Q maps, maps of the average, and of the variance, of α , β , P and Q are
 15 computed. The average and the variance are computed by standard statistical techniques (see, e.g., Tou and Gonzalez, 1974, Pattern Recognition Principles, Addison-Wesley Publishing Co. Inc.). In addition, texture maps for each of α , β , P and Q are computed. Texture maps can be computed in a number of ways (for a description of the concepts of image texture see, e.g.,
 20 Haralick, 1982, "Image Texture Survey", in Handbook of Statistics, Krishniah and Kanal, editors, Vol. 2, 399), e.g., with aid of the computation of the two dimensional autocorrelation function according to the following equation :

$$K_{\phi}(\rho) = e^{-\lambda_{\phi}\rho} \cos(\omega_{\phi}\rho),$$

where, ρ is a translational distance between pixels and ϕ is a translational
 25 angle between the pixels, defined as the angle between the horizontal axis and the line joining the origin of the coordinate system to the pixel under consideration. λ_{ϕ} and ω_{ϕ} are constants of the autocorrelation function. As ϕ varies from 0° to 360° λ_{ϕ} and ω_{ϕ} take on a set of possible values. the parameters that describe the set of possible values of λ_{ϕ} and ω_{ϕ} are the

parameters that characterize the texture. Since the texture assists in the classification process it is important to have a fairly simple representation for the set of values it comprises. To this end, the envelope of the set of maximal values of λ_ϕ and ω_ϕ is chosen to be an ellipse. In order then to characterize the texture, the parameters of the ellipse of the maximal values of λ_ϕ and ω_ϕ have to be computed. An ellipse is described by three parameters, its minor axis, its major axis and the orientation of the ellipse in the plane of its definition. All in all, to characterize the texture, seven parameters are required, three that characterize the ellipse of the maximal values of λ_ϕ , three that characterize the ellipse of the maximal values of ω_ϕ and one for the angle between the axes of the two ellipses. Hence, seven texture maps are computed for each of the thermophysical constants α, β, P and Q . Hence, initially twenty eight texture maps are required. The maps of α, β, P and Q , and of their average and variance, and the texture maps of α, β, P and Q define a set of characteristic maps of the selected region.

Areas of the selected region containing underground structures have surface temperatures that are very slightly different from those of the surroundings. These very slight temperature differences give rise to temperature maps of very low contrast in which it is difficult to distinguish between normal ground areas and those covering underground structures. The characteristic maps of the selected region serve to augment the temperature maps and to increase the contrast between these two types of grounds. Since there are a large number of maps and a large number of pixels per map, statistical methods are used for associating, or classifying, the pixels of the selected region with various backgrounds and targets therein.

In the classification process the selected region is divided into classes. Initially the number of classes is as the number of pixels, however, in order for the pattern recognition process to be successful, the number of classes should be representative of the number of types of different

backgrounds and targets, i.e., enquiry sectors, in the selected region. The classification process is carried out in two stages; the learning stage and the association stage. In the learning stage the number of classes in the selected region is determined, whereas in the association stage each of the pixels in the maps is associated with a class. To perform the classification a suitable statistical function describing the distribution of pixel values is chosen. For example, but by no means binding, a sum of weighted Gaussians, i.e. a poly-Gauss, can be chosen:

$$P(\vec{s}) = \sum_{i=1}^m \omega_i N_i(\delta_i, \vec{s})$$

10 where:

$N_i(\delta_i, \vec{s})$ is the i^{th} Gaussian in the sum,

ω_i is the weight of the i^{th} Gaussian in the sum,

\vec{s} is a vector whose components are the elements of the set of characteristic maps of the selected region,

15 m is the number of classes, and

δ_i represents the parameters of the i^{th} Gaussian in the sum (for the properties of Gaussian distributions see - Tou and Gonzalez, *ibid.*).

The learning stage consists of determining the values of m , ω_i , and δ_i , or, if a different distribution is chosen, the equivalent parameters. ω_i and δ_i are chosen such that the poly-Gauss distribution density is maximal for a given vector \vec{s} . The value of m is determined by including in the weighted sum only those terms for which :

$$\omega_i / \Delta \omega_i < \nu$$

25 where, ν is chosen optimally by trial and error to include enough terms in the sum so that the pattern recognition process is successful, whilst on the other hand it should be as small as possible so as to keep the computational complexity to a minimum. The error in computing ω_i , $\Delta \omega_i$, is determined using Fisher's matrix (Rao, 1973. Linear Statistical Inference and its Application. Wiley). The value $\nu = 2$ has been found to be optimal in a

number of pattern recognition experiments that were conducted.

The association stage is performed by computing for each pixel, say the i^{th} , the probability, P_{ik} , that it belongs to class, k , for each class in the selected region, using, e.g., Bayes' equation (see, Rolston, Principles of Artificial Intelligence and Expert Systems Development, McGraw-Hill, 99).
 5 The decision for associating the i^{th} pixel with the k^{th} class is made by determining the maximal value of

$$\tilde{P}_{i,k} = P_{ik} - \gamma \Delta P_{ik},$$

for a fixed value of i as k runs over all the classes. The error, ΔP_{ik} , in
 10 computing the probability, P_{ik} , can be determined using Fisher's matrix (Rao, 1973.). The constant γ , is determined empirically in controlled experiments by finding the minimum set of characteristic maps that enable target detection to a required degree of accuracy. For $\gamma = 0$ the full set of characteristic maps has to be included in the pattern recognition process giving rise to maximum
 15 complexity in the computational process. In a certain set of controlled experiments it was found that $1 \leq \gamma \leq 3$. Invariably, the choice $\gamma = 2$ has been found to give good results for a minimal computational load.

In the manner described, the class to which each pixel belongs is determined, hence effecting the association stage and thereby completing the classification
 20 process.

Having determined the value of γ , a quality factor, $Q(\bar{s})$, is defined in order to effect the pattern recognition process:

$$Q(\bar{s}) = \tilde{P} - \gamma \Delta \tilde{P}$$

where, \tilde{P} is the average probability of associating each element of a set to its
 25 class, and can be computed using Bayes theorem. $\Delta \tilde{P}$, is the error in computing the probability \tilde{P} , and can be computed using Fisher's matrix. The constant γ , is the same as that discussed in the foregoing. The pattern recognition process entails determining that set of characteristic maps that makes $Q(\bar{s})$ maximal. In other words the value of $Q(\bar{s})$ is a criterion for

the quality of the classification of the selected region. The process then is carried out as follows; choose a set of characteristic maps, perform the classification process and compute $Q(\bar{s})$. If $Q(\bar{s})$ is not close to the value 1, then choose another set of characteristic maps, perform the classification
5 process again and re-compute $Q(\bar{s})$. If the value of $Q(\bar{s})$ is close to 1, then an optimal set of characteristic maps has been found and the classification process is declared successful. If the value of $Q(\bar{s})$ is not close to 1, then the process is repeated until the classification process can be declared successful. An underground structure is then an anomaly in the selected
10 region, i.e., any area in the selected region that does not belong to a defined class, is then declared to be an underground structure. Normally, the pattern recognition process starts off with a very large set of characteristic maps and the computational load is very heavy. In order to partially reduce the computational load, the pattern recognition process is performed with a
15 priorly optimized set of characteristic maps. This optimization is achieved by performing a least squares calculation (see - Lawson and Hanson, Solving Least Squares Problems. Prentice-Hall) on $Q(\bar{s})$ using a weighted set of characteristic maps in order to find the relative weights of the characteristic maps in their contribution to $Q(\bar{s})$. Those characteristic maps having a small
20 weight are discarded.

Sometimes there may be prior information as to the form of the underground structures. In such an event the classification process can be enhanced and the anomalies in the selected region can be sorted by geometrical form, making the identification of an underground structure much
25 more reliable.

The pattern recognition process is summarized in **Fig. 6**. The complete set of characteristic maps is initially optimized at stage 46 using least squares. The initially optimized set of characteristic maps is then used to classify the pixels into classes (block 47), by performing the learning and

association stages as described above. The quality factor is then computed, at stage 48, and its value is checked, stage 49. If the value of the quality factor is not maximal, then a new set of characteristic maps is chosen from the initially optimized set of characteristic maps (process 50). Processes 47, 48, 5 49 and 50 are continually performed until an optimal value for the quality factor is obtained, at the stage pattern recognition is achieved (block 51). The pattern recognition process can also include an additional geometrical classification process for determining the shape of the detected object. This is particularly useful when detecting underground objects of a known shape. In 10 general, the anomalous region defining the underground object may be larger than the object to be detected, in which case distribution of the anomalous pixels can be studied for the known geometrical trends (for standard methods see Tou and Gonzalez, *ibid.*).

Fig. 7 schematically illustrates a system for obtaining 15 temperature/emissivity maps of a selected object and further recognition of segments thereof based on the obtained maps and some additional parameters (such as thermophysical constants and meteorological data). An object 60 (for example, a selected region on or above the earth) emits electromagnetic radiation on to an optics 62 via which it is transmitted to a multi-channel 20 sequential filter 64 (for example, a rotational filter). The filter 64 produces N radiation portions in N respective spectral bands in sequence. Intensities of the obtained N radiation portions are then detected by a detector 66. "N" analogous readings of the electromagnetic radiation obtained by the detector 66 are further converted into the digital form and transmitted to a processing 25 unit 68 where they are stored for further processing. M*N obtained digitized readings of the radiation emitted from the object 60 are processed in the unit 68 as a system of equations built according to formula (1). Values of the temperature (and/or the emissivity parameters or values), being solutions of these equations, are further transmitted to a pattern recognition processor 72

for building respective temperature and emissivity descriptive maps, per pixel, i.e. per segment of the object. However, data on the temperature and emissivity (if applicable) can be directly transmitted to display means 78, for optional indication. The pattern recognition processor 72 also receives
5 meteorological and thermophysical data schematically shown as block 80, and processes the temperature and emissivity data received from the processing unit 68 to produce a file 74 being a contrast descriptive map of the object and a file 76 being a classified image thereof. The contrast descriptive map 74 is a characteristic map based on a combination of the
10 temperature and emissivity descriptive maps, and the classified image 76 is a result of the pattern recognition processing based on the map 74 and the data 80. The display means 78 serves for graphical representation of the obtained files 74 and 76. The system illustrated in the drawing is adapted to obtain information on the electromagnetic radiation from the object 60 with
15 the aid of a movable platform (such as a helicopter), and to process it. To this end, the control unit 70 of the processing unit 68 may receive data (schematically shown as block 82) on the velocity of the platform's movement with respect to the object. The unit 68 is provided with software means capable of registering the descriptive maps of temperature and
20 emissivity with the platform movement. All the above-described operations are synchronized by a control unit 70 of the processing unit 68, which generates M successive synchronizing signals per each segment of the object 60. Each of these M signals simultaneously activates optics 62, filter 64, detector 66 and processing unit 68 for performing and recording each of
25 the M measurements of the radiation in N spectral bands in sequence.

CLAIMS:

1. A method of determining temperature of an object by remote sensing, comprising:
 - acquiring electromagnetic radiation data from the object in N spectral
 - 5 bands,
 - deriving temperature value from said data using a system of equations, each describing the electromagnetic radiation that is emitted from the object in said band as a function of temperature and emissivity of the object:
the method being characterized in that,
 - 10 - said electromagnetic radiation is measured M times, each time in N said spectral bands, thus obtaining $N \cdot M$ readings,
 - a system of $N \cdot M$ equations is formed, each describing the electromagnetic radiation that is emitted from the object in said band as a function of temperature T and emissivity ε of the object, wherein the
 - 15 emissivity ε is a function of at least two arguments being temperature T and wavelength λ : said system comprising $N \cdot M$ readings of the electromagnetic radiation and $M+P$ unknowns which include M values of the object's temperature corresponding to said respective M measurements of the electromagnetic radiation, and P parameters, wherein $P \geq 2$: said parameters
 - 20 belonging to a selected mathematical form of the emissivity function:
 - solving said system of $N \cdot M$ equations, thus deriving temperature of the object at any one of the M moments of said electromagnetic radiation measurement, wherein M is a natural number of the set [1, 2, 3...].
- 25 2. A method of determining emissivity function of an object by remote sensing, comprising
 - acquiring electromagnetic radiation data from the object in N spectral bands by measuring it M times, each time in N said spectral bands, thus obtaining $N \cdot M$ readings,

- forming a system of $N \times M$ equations, each describing the electromagnetic radiation that is emitted from the object in one of said bands as a function of temperature T and emissivity ε of the object, wherein the emissivity ε is a function of at least two arguments being temperature T and wavelength λ ; said system comprising $N \times M$ readings of the electromagnetic radiation and $M+P$ unknowns including M values of the object's temperature corresponding to said respective M measurements of the electromagnetic radiation, and P parameters, wherein $P \geq 2$; said parameters belonging to a selected mathematical form of the emissivity function;
 - 10 - solving said system of $N \times M$ equations to derive said P parameters, thereby restoring the emissivity function of the object.
3. The method according to Claim 1 or 2, comprising:
- 15 - selecting said emissivity function to take constant values within respective spectral bands thus considering P equal to N , and
 - forming said system of $N \times M$ equations to comprise $N \times M$ readings of the electromagnetic radiation and $M+N$ unknowns; said $M+N$ unknowns including M values of the object's temperature corresponding to said respective M measurements of the electromagnetic radiation and N values of emissivity for said respective N spectral bands.
- 20 bands.
4. The method according to any one of the preceding claims, wherein each reading obtained from said M measurements of the electromagnetic radiation
- 25 in N spectral bands is digitized and stored in a computer memory for further computerized processing, said processing comprising substituting the digitized $M \times N$ readings of the electromagnetic radiation into said $M \times N$ equations, and solving thereof.

5. The method according to any one of the preceding claims, wherein said measurements are provided in the infrared spectrum.
6. The method according to any one of the preceding claims, wherein said
5 equations are integral.
7. The method according to Claim 6, wherein said equations are Fredholm equations relating to emissivity.
- 10 8. The method according to Claim 6 or 7, wherein each of said M*N equations describes the electromagnetic radiation that is emitted from the object in one of said bands as a function of the temperature and the respective emissivity of the object, the emissivity, in turn, being a known function of temperature, wavelength and a known number of unknown parameters: said
15 parameters being introduced as additional unknowns into said system of equations for further obtaining their values upon solving the system.
9. The method according to Claim 8, wherein said known function is represented as a sum of a known number of terms of two other functions, a
20 first of which being dependent only on temperature and a known number of unknown parameters, and a second being dependent only on wavelength.
10. The method according to Claim 8, wherein said known function is represented by a polynomial expansion having K unknown coefficients, said
25 coefficients being introduced into the system of equations as unknown parameters to be determined among said unknowns upon solving said system.
11. The method according to any one of claims 1, 8 to 10, for non-contact temperature measurement of heated semiconductor materials and samples

during manufacture thereof.

12. The method according to any one of the preceding claims, intended for deriving temperature and/or emissivity descriptive maps of the object,
5 wherein the temperature and/or emissivity is determined with respect to a pre-selected plurality of representative segments of the object, and mapping each of the determined values to a respective pixel of said descriptive map.

13. The method according to Claim 12, wherein the object comprises a plurality of sub-objects having different temperatures and/or emissivities and
10 dislocated in a selected region.

14. The method according to Claim 13, for detection said sub-objects with a background of the ground and surrounding atmosphere, comprising the steps of:

- 15 - acquiring meteorological data indicative of climatic conditions of the selected region on the ground and/or the surrounding atmosphere:
- recording the acquired electromagnetic radiation and meteorological data by means of suitable data recording means;
- storing the so-recorded data in suitable data storage means and
20 deriving from the so-stored data, descriptive maps of the selected region: and
- feeding data of said descriptive maps into pattern recognition processor means to classify the pixels of said maps of said selected region, whereby the desired object detection is achieved.

25

15. The method according to Claim 14, wherein said meteorological data are obtained from meteorological stations.

16. The method according to Claim 14 or 15, comprising providing a single

scanning pass of the selected region (i.e. $M=1$) for the detection if a pronounced temperature and/or emissivity differential is revealed for representative segments of the object.

- 5 17. The method according to Claim 14 or 15, wherein said descriptive maps describe temperature, emissivity and albedo, wherefrom a set of characteristic maps of the selected region are derived by incorporating suitable reference data.
- 10 18. The method according to Claim 17, wherein an optimal set of characteristic maps of the selected region is chosen.
19. The method according to any one of Claims 14 to 18, wherein the pixel classification comprises defining a number of classes and associating the
15 pixels in the selected region with said classes.
20. The method according to any one of Claims 14 to 19, wherein a quality function is defined and the pattern recognition process entails determining that set of characteristic maps that makes the quality function maximal.
- 20 21. The method of any one of Claims 14 to 20, wherein the acquisition of electromagnetic radiation is performed by near range scanning.
22. The method of any one of Claims 14 to 20, wherein the acquisition of
25 electromagnetic radiation is performed by remote scanning.
23. The method of any one of Claims 14 to 22, wherein the scanning of the selected region is performed with at least five ground oriented sensors operating, respectively, in the 3-4 μ , 4-5 μ , 8-10 μ , 10-12 μ and the near

infrared and visible spectral bands, and there is provided at least one further sensor for measuring electromagnetic radiation from the space above, operating in the 0.4-2 μ spectral band.

5 24. The method according to any one of Claims 14 to 23, wherein said classifying processor means in which the pixels of the characteristic maps of the selected region are classified into classes, makes use of a poly-Gauss expansion to describe the statistical distribution of the pixels and Bayes' method to sort the pixels into classes.

10

25. The method according to Claims 14 to 24, wherein said pattern recognition processor means also include additional geometrical classification means for determining the shape of the detected object.

15 26. The method according to any one of Claims 14 to 25, adapted for real time temperature and/or emissivity mapping of a plurality of selected regions to be observed, wherein the step of acquisition of said electromagnetic radiation data is provided in real time by equipment mounted on a movable platform while displacing along said plurality of selected regions: and
20 wherein the steps of recording and storing the acquired electromagnetic radiation and meteorological data and further deriving, from the so-stored data, descriptive maps of the selected region are registered with the platform displacement.

25 27. The method according to Claim 26, comprising automatic recognition of objects positioned along or on the course of the moving platform.

28. The method according to Claim 27, additionally comprising initiating an alarm and automatic adjusting the course of the vehicle whenever an obstacle

is recognized.

29. A system for remotely determining temperature and/or emissivity function of an object, said system comprising:

5 scanning means for acquiring electromagnetic radiation data from the object M times, each time in N spectral bands, thus obtaining N*M readings of the electromagnetic radiation, wherein M is a natural number of the set [1, 2, 3 ...];

 means for recording and storage said N*M readings in the digital
10 form:

 computational means for processing said N*M readings of the electromagnetic radiation as a system of N*M equations comprising M unknown values of temperature and at least P unknown parameters, wherein $P \geq 2$; said parameters belonging to a selected mathematical form of the
15 object's emissivity function (ϵ) of at least two arguments being temperature T and wavelength λ ;

 display means for displaying one or more of said unknowns obtained upon solving said system of equations, or derivatives therefrom.

20 30. The system according to Claim 29, wherein said scanning means are capable of acquiring the electromagnetic radiation from a plurality of representative segments of the object, and said computational means are capable of processing the acquired data, for deriving and displaying temperature and/or emissivity descriptive maps of the object.

25

31. The system according to Claim 29 or 30, wherein said scanning means comprise a plurality of sensors capable of simultaneously measuring electromagnetic radiation in a number of spectral bands.

32. The system according to Claim 29 to 30, wherein the scanning means comprise a spatial optical filter divided into a number of sites for simultaneous acquiring the electromagnetic radiation from said plurality of respectively located segments of the object; each said site having N zones
5 responsible for splitting the radiation acquired by the site into N spectral bands, thereby acquiring the electromagnetic radiation in all N spectral bands simultaneously.

33. The system according to Claim 29 or 30, wherein the scanning means comprise a rotatable optical filter for acquiring electromagnetic radiation in
10 said N spectral bands in sequence.

34. The system according to any one of the Claims 29 to 33, wherein said scanning means are capable of remote scanning.

15 35. The system according to any one of the Claims 29 to 33, wherein said scanning means are designed for close range scanning.

36. The system according to any one of Claims 29 to 35, wherein said scanning means comprise at least five ground oriented sensors operating,
20 respectively, in the 3-4 μ , 4-5 μ , 8-10 μ , 10-12 μ and the near infrared and visible spectral bands and at least one space oriented sensor operating in the 0.4-2 μ spectral band.

37. The system according to any one of Claims 29 to 36, capable of object
25 detecting in a selected region having a background including the ground and/or the surrounding atmosphere, further comprising:

- means for acquiring meteorological data indicative of climatic conditions of the selected region and the surroundings;
- means for recording said meteorological data;

- 45 -

- data storage means for storing the recorded meteorological data;
-computational means for deriving from the stored meteorological data and the data on the electromagnetic radiation, descriptive maps of the selected region; and

5 - pattern recognition processor means for classifying the pixels of said maps.

38. The system according to Claim 37, wherein said means for acquiring meteorological data are associated with meteorological stations.

10

39. The system according to Claims 37 or 38, wherein said computational means are capable of deriving from said descriptive maps a set of characteristic maps.

15 40. The system according to Claim 37 to 39, wherein said processor means comprise optimizing means for selecting an optimal set of characteristic maps which is subjected to pixel classification.

41. The system according to any one of Claims 37 to 40, wherein the pattern
20 recognition processor means comprises pixel classification means in which a number of classes is defined whereby the classified pixels are statistically associated with the classes.

42. The system according to any one of Claims 37 to 41, wherein the pattern
25 recognition processor means is capable of functioning based on a poly-Gauss expansion for determining the statistical distribution of the pixels, and means based on Bayes's method for sorting pixels into classes.

43. The system according to any one of Claims 37 to 42, wherein said

pattern recognition processor means comprises quality factor evaluation means.

44. The system according to any one of Claims 37 to 43, wherein the pattern
5 recognition processor means includes additional geometrical classification means for determining the shape of the detected object.

45. The system according to any one of Claims 37 to 44, wherein the
scanning means and the data recording means are positioned on any movable
10 platform, whereas the data storage means, computational means, classification means and pattern recognition means are placed on the ground.

46. The system according to any one of Claims 37 to 44, being portable and mountable on a movable platform.

15 47. The system according to Claim 45 or 46, wherein said computational means are adapted to register the recorded and stored data of the acquired electromagnetic radiation with the platform's movement to obtain a real time mapping and pattern recognition.

20 48. The system according to any one of Claims 45 to 47, wherein said pattern recognition processor means are capable of automatic recognition of objects positioned along or on the course of the moving platform.

25 49. The system according to Claim 48, additionally comprising means for initiating an alarm.

50. The method according to any one of Claims 14, 15, 17 to 26, for detection of underground structures, comprising extracting from the recorded

data physical information characterizing heating and cooling processes that take place at the ground surface and below it by applying an equation of energy balance and a set of thermophysical constants, processing said information for detecting regions having different thermal properties, in the region selected for scanning, and classifying thus revealed thermophysical inhomogeneous regions by said pattern recognition processor means, thereby identifying the underground structures.

51. The method according to Claim 50, comprising derivation of the descriptive and characteristic maps based on Planck's equation, describing the electromagnetic radiation that is emitted from and reflected by the ground.

52. The method according to Claim 51, wherein said characteristic maps comprise maps of thermal inertia, thermal flux, coefficient of heat transfer and coefficient of mass transfer.

53. The system according to Claims 37 to 47, wherein said pattern recognition processor means are capable of extracting from the recorded data physical information characterizing heating and cooling processes that take place at the ground surface and below it by applying an equation of energy balance and a set of thermophysical constants, processing said information for detecting regions having different thermal properties, in the region selected for scanning, and classifying thus revealed thermophysical inhomogeneous regions, thereby enabling identifying and displaying the underground structures.




FIG. 1a
SUBSTITUTE SHEET (RULE 26)

2/8

From FIG. 1a

1

5

PROCESSING THE SYSTEM OF $N \times M$ EQUATIONS,
IN EACH OF WHICH THE EM RADIATION
VALUE V IN A PARTICULAR SPECTRAL BAND Δ_i
IS A FUNCTION OF TEMPERATURE T AND
EMISSIVITY ϵ OF THE SAMPLE

$$V_{T_j}^i = f(T_j, \epsilon_i)$$

6

OBTAINING M SUCCESSIVE VALUES OF
TEMPERATURE OF THE OBJECT

$\langle T_1 \dots T_j \dots T_M \rangle$, AND

OBTAINING N VALUES OF EMISSIVITIES

$\langle \epsilon_1 \dots \epsilon_i \dots \epsilon_N \rangle$ FOR N SPECTRAL BANDS,
RESPECTIVELY

FIG. 1b

3/8




FIG. 2




FIG. 3

5/8




FIG. 4a




FIG. 4b

SUBSTITUTE SHEET (RULE 26)

6/8




FIG. 5

7/8




FIG. 6
SUBSTITUTE SHEET (RULE 26)

8/8




FIG. 7

31

Underground Physical Non-uniformity Detecting Method.

The invention is related with geological recognition methods and may be used in mineral products searching, geological investigations, etc. The invention goal is the improvement of underground non-uniformity detection method by means of low contrast in the detection of thermo-physical properties objects.

This method may be realized in the following way:

Twice remote Earth surface thermo surveying (mapping) must be done on the tested area territory. First surveying must be done after sunset, and second – before sunrise. Some reference zones within tested area must be selected. These selected zones must be characterized by presence of differences of thermo-physical properties objects.

Night thermo contrast inversion moment must be defined by means of a few methodical surveyings. That is the moment, when different thermo inertia mineral bodys will be equal on temperature during the night. The following data processing must be done depending on above mentioned thermo inversion effect presence or absence. If thermo inversion effect present, subtraction of two thermo maps must be used in following data analysis. If thermo inversion effect absent, adding of two maps must be used. If resultant thermo map has an anomalous, this map may be used for underground irregularity detection.

Optimisation for remote recognition season choice must be done with night thermo inversion moment for different thermo inertia bodys taking into account. If thermo inversion effect is present, surveying must be done at the time, when the inversion moment is maximum removal from sunset moment. If thermo inversion effect is absent, surveying must be done at the time of maximum minerals temperature difference, discovered on reference zone during the night.

This method provides the low contrast thermo non-uniformity detection.



СОЮЗ СОВЕТСКИХ
СОЦИАЛИСТИЧЕСКИХ
РЕСПУБЛИК

(19) **SU** (11) **1383259** **A1**

(SD) 4 G 01 V 9/00

ГОСУДАРСТВЕННЫЙ КОМИТЕТ СССР
ПО ДЕЛАМ ИЗОБРЕТЕНИЙ И ОТКРЫТИЙ

THE BRITISH LIBRARY

4 JUL 1988

SCIENCE REFERENCE AND
INFORMATION SERVICE

ОПИСАНИЕ ИЗОБРЕТЕНИЯ К АВТОРСКОМУ СВИДЕТЕЛЬСТВУ

(21) 4022847/24-25
(22) 13.02.86
(46) 23.03.88. Бюл. № 11
(71) Производственное геологическое объединение по региональному изучению геологического строения территории страны "Аэрогеология"
(72) О.В.Ляшенко, Ю.А.Афанасов, И.Г.Мельников и С.М.Калимулин
(53) 550.83(088.8)
(56) Авторское свидетельство СССР № 913314, кл. G 01 V 9/00, 1982.
Лялько В.И. и др. Геотермические поиски полезных ископаемых. - Киев: Наукова думка, 1979, с. 19-20.

(54) СПОСОБ ОБНАРУЖЕНИЯ ПОДЗЕМНЫХ НЕОДНОРОДНОСТЕЙ С РАЗЛИЧНЫМИ ТЕПЛОФИЗИЧЕСКИМИ СВОЙСТВАМИ
(57) Изобретение относится к геотермическим методам разведки и может быть использовано при поисках полезных ископаемых. Цель - расширение возможностей способа за счет выявления мало контрастных по теплофизическим свойствам объектов. Способ реализуется путем двукратного измерения теплового поля в течение одной ночи при оптимизации сезонного времени определения и интерпретации результирующего поля в зависимости от положения точки ночной инверсии.

(19) **SU** (11) **1383259** **A1**

2/4

Редактор Е.Папп Составитель Н.Грязнов
Техред Л.Сердюкова Корректор Л.Пилипенко

Заказ 1293/43 Тираж 522 Подписное
ВНИИПИ Государственного комитета СССР
по делам изобретений и открытий
113035, Москва, Ж-35, Раушская наб., д. 4/5

Производственно-полиграфическое предприятие, г.Ужгород, ул.Проектная, 4

3/4

1

1383259

2

Изобретение относится к геотермическим методам разведки и может быть использовано при поисках полезных ископаемых, инженерно-геологических изысканиях и т.д.

Цель изобретения - расширение возможностей способа обнаружения подземных неоднородностей за счет выявления малоконтрастных по теплофизическим свойствам объектов.

Способ реализуется следующим образом.

На исследуемой территории (полигоне) проводят двукратную дистанционную тепловую съемку поверхности Земли. Первое измерение осуществляют после захода, а второе - в предассветное время перед восходом Солнца.

В пределах полигона выбирают эталонные участки, характеризующиеся наличием пород с различными теплофизическими свойствами. На выбранных участках, например, с помощью режимных наблюдений, определяют время ночной инверсии температурных контрастов, т.е. время, когда температуры пород с различной тепловой инерцией становятся равными в течение ночи.

В зависимости от наличия или отсутствия ночной инверсии обработку данных, полученных после проведения двукратной дистанционной тепловой съемки на полигоне, производят следующим образом.

При наличии ночной инверсии температурных контрастов результирующее тепловое поле определяют по разности полученных температур, а при ее отсутствии - по их сумме. По аномальным значениям результирующего теплового поля выносят суждение о наличии подземных неоднородностей.

Выбор оптимального сезонного периода для проведения дистанционных измерений также производят с учетом времени ночной инверсии температурных контрастов пород с различной тепловой инерцией.

При наличии ночной инверсии измерения проводят в течение периода, когда время инверсии максимально удалено от захода Солнца. При отсутствии ночной инверсии измерения осуществляют в период наибольших перепадов температур пород на эталонном участке в течение ночи.

Использование способа обеспечивает выявление малоконтрастных по теплофизическим свойствам неоднородностей.

Ф о р м у л а и з о б р е т е н и я

Способ обнаружения подземных неоднородностей с различными теплофизическими свойствами, включающий двукратное проведение дистанционной тепловой съемки поверхности Земли, одно из которых производится в предассветное время, обработку полученных данных и суждение о наличии неоднородностей, отличающийся тем, что, с целью расширения возможностей способа за счет выявления малоконтрастных по теплофизическим свойствам объектов, второе измерение проводят после захода солнца, определяют время ночной инверсии температурных контрастов пород с различной тепловой инерцией, при наличии ночной инверсии результирующее тепловое поле определяют по разности полученных температур, а при ее отсутствии - по их сумме.

Составитель Н.Грязнов

Редактор Е.Папп

Техред Л.Сердюкова

Корректор Л.Пилипенко

Заказ 1293/43

Тираж 522

Подписное

ВНИИПИ Государственного комитета СССР
по делам изобретений и открытий

113035, Москва, Ж-35, Раушская наб., д. 4/5

Производственно-полиграфическое предприятие, г.Ужгород, ул.Проектная, 4

INTERNATIONAL SEARCH REPORT

Information on patent family members

International Application No

PCT/IL 98/00568

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
EP 0143282 A	05-06-1985	DE 3343043 A DE 3414984 A DD 229213 A JP 1796595 C JP 5005051 B JP 60140131 A US 4974182 A DD 229212 A	05-06-1985 24-10-1985 30-10-1985 28-10-1993 21-01-1993 25-07-1985 27-11-1990 30-10-1985
EP 0420108 A	03-04-1991	LU 87595 A AT 107021 T AU 639029 B AU 6418590 A CA 2067248 A DE 59006014 D DK 420108 T WO 9104472 A ES 2056328 T IE 64270 B JP 6500387 T PT 95405 A,B RU 2083961 C	07-05-1991 15-06-1994 15-07-1993 18-04-1991 26-03-1991 14-07-1994 29-08-1994 04-04-1991 01-10-1994 26-07-1995 13-01-1994 29-05-1992 10-07-1997
US 5377126 A	27-12-1994	NONE	
GB 2131649 X A	20-06-1984	FR 2537289 A SE 8306608 A	08-06-1984 02-06-1984
WO 9711340 X A	27-03-1997	AU 6888596 A CA 2231166 A CN 1200808 A EP 0848807 A	09-04-1997 27-03-1997 02-12-1998 24-06-1998
DE 4134313 A	22-04-1993	NONE	

INTERNATIONAL SEARCH REPORT

International Application No.

PCT/IL 98/00568

A. CLASSIFICATION OF SUBJECT MATTER
IPC 6 G01J5/60

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 6 G01J

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	<p>✱ EP 0 143 282 A (DEUTSCHE FORSCH LUFT RAUMFAHRT) 5 June 1985</p> <p>see page 5, line 6 - page 19, line 14 see page 22, line 19 - line 20 ---</p>	1-6, 21, 23, 29-32, 45, 46
X	<p>✓ EP 0 420 108 A (EURATOM) 3 April 1991</p> <p>see the whole document ---</p>	1-6, 8-10, 29, 30
X	<p>US 5 377 126 A (FLIK MARKUS I ET AL) 27 December 1994</p> <p>see the whole document ---</p>	1-6, 8-11, 29, 30
-/--		

☒ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

* Special categories of cited documents:

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search

2 March 1999

Date of mailing of the international search report

12/03/1999

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax: (+31-70) 340-3016

Authorized officer

Ramboer, P

INTERNATIONAL SEARCH REPORT

International Application No

PCT/IL 98/00568

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT		
Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	GB 2 131 649 A (BRITISH AEROSPACE) 20 June 1984 see the whole document ----	1,12, 50-53
A	WO 97 11340 A (3T TRUE TEMPERATURE TECHNOLOGI ;GLAZMAN EVGENY (IL)) 27 March 1997 see page 8, line 3 - page 9, line 4 see page 9, line 15 - line 38 ----	1,2,5
A	* KEALY P S ET AL: "SEPARATING TEMPERATURE AND EMISSIVITY IN THERMAL INFRARED MULTISPECTRAL SCANNER DATA: IMPLICATIONS FOR RECOVERING LAND SURFACE TEMPERATURES" IEEE TRANSACTIONS ON GEOSCIENCE AND REMOTE SENSING, vol. 31, no. 6, 1 November 1993, pages 1155-1164, XP000432082 see the whole document ----	1,2,12, 29,30, 50,51
A	DE 41 34 313 A (DEUTSCHE AEROSPACE) 22 April 1993 see the whole document ----	1,50-53
A	* RIICHI NAGURA ET AL: "OPTICAL SENSOR SYSTEM FOR JAPANESE EARTH RESOURCES SATELLITE-1" NEC RESEARCH AND DEVELOPMENT, vol. 33, no. 2, 1 April 1992, pages 226-235, XP000310833 see the whole document ----	1,4,12, 23,29, 45,46,53
A	DATABASE WPI Section EI, Week 8839 Derwent Publications Ltd., London, GB; Class S03, AN 88-277509 XP002095191✓ & SU 1 383 259 A (AEROGEOLOGIYA) , 23 March 1088 see abstract -----	1,12,13, 25,26, 29,50-53